Commercial Roof Renewal Proposal

Prepared for **Dana Ortiz**, Valley Logistics Partners LLC

Property	4800 E Jensen Ave, Fresno, CA 93725
Roof area	42,000 sq ft · existing modified bitumen (approx. 18 years old)
Proposal #	MCC-2026-0142
Date	October 24, 2026
Valid until	November 23, 2026
Prepared by	Mike McCurdy · (650) 952-0233

OUR RECOMMENDATION
Silicone Renewal — 30-Year NDL Full System
30-year warranty · $180,940.00

VS. A NEW ROOF
+50% more warranted years
and up to 45% less than a full replacement, with no tear-off or shutdown

Summary

Your roof membrane is aged but still watertight over most of the building. A silicone restoration seals it, reflects Central Valley heat and carries a manufacturer NDL warranty of up to 30 years without a tear-off or closing the warehouse.

What We Found

We walked the full roof on Oct 20. The modified bitumen is chalking and cracking from sun exposure, with seam lifts at wall transitions and ponding in two low areas near the center drains. Core samples showed dry insulation.

Key issues

- Sun damage and surface cracking across most of the field area
- Seam lifting at parapet walls and around HVAC curbs
- Ponding water (1–2 in.) at two center drains
- Four drain strainers missing or broken

Scope of Work

- Remove and replace all soft spots, dry-rot wood and failed membrane before any other work.
- Clear debris, sweep and blow off the roof; clear and test every drain.
- Power-wash the roof, then wash again with the manufacturer-recommended cleaner.
- Remove and replace every rusted, loose, missing, crushed or incorrect flashing, perimeter flashing, vent and drain.
- Install new screens or grates on every drain; confirm an overflow drain on every low-slope area.
- Fill all low spots and potential ponding areas.
- Chalk-line the entire roof into 10 × 10 ft squares; roll on primer at 1 gallon per square to the manufacturer's specification.
- Seal every detail: seams, exposed fasteners, flashings, cap metal, gravel stop, nosing, vents, pipe collars, drains, straps, seismic braces, brackets, pitch pockets, sleepers, stanchions, standoffs, skylights, panels and sun tubes.
- New grid, then the base coat at 1–2 gallons per square in one color.
- 20 to 30-year NDL systems: a third grid and a contrasting top coat at 2–2.5 gallons per square.
- Manufacturer representative inspects the roof and mil readings on every commercial job.
- Clean the roof, gutters, grounds and surrounding areas at the end of every work day; final roof walk with the owner or our quality supervisor, with any item found scheduled and completed.

Investment Options

Every option follows the full McCurdy Method. Longer warranties add coats, measured by the grid, and every warranty is issued in writing by the manufacturer.

Option	Coats	Warranty	Investment	$ / sq ft
Silicone Renewal — 10-Year Warranty	Primer 1 gal + silicone 1–2 gal per 100 sq ft; APOC minimum 23 total dry mils	10 yrs	$117,940.00	$2.81
Silicone Renewal — 15-Year Warranty	Primer 1 gal + silicone 1–2 gal per 100 sq ft; APOC minimum 31 total dry mils	15 yrs	$145,240.00	$3.46
Silicone Renewal — 30-Year NDL Full System RECOMMENDED	Primer 1 gal + base 1–2 gal + contrasting top coat 2–2.5 gal per 100 sq ft; APOC minimum 47 total dry mils	30 yrs	$180,940.00	$4.31

Included in every option

- Replace 6 roof drain strainers and clear drain lines — $1,110.00
- Re-flash 14 HVAC curbs with reinforced silicone detail — $1,330.00

Renewal vs. Replacement

	Tear-off & replace	McCurdy renewal (30-year)
Typical cost	Full replacement price	Up to 45% less than a full replacement by a commercial roofing company
Warranty	Typically up to 20 years	30-year manufacturer warranty (50% more years)
Business disruption	Weeks of noise, debris, open roof	Building stays open
Landfill waste	Old roof hauled to landfill	Existing roof stays in place
Energy	Depends on new membrane	Reflective white surface lowers roof temperature
Future	Start over at end of life	Re-coat to extend life again

Typical figures from McCurdy Coatings projects. Your price above is firm for this roof.

Why a much lower bid can't carry the same warranty

- A 30-year NDL system needs 4 to 5.5 gallons of primer and silicone on every 100 sq ft; that material has to be in the price.
- If one required step is skipped, or any area is under thickness, the manufacturer can refuse to issue the warranty.
- Ask every bidder for the manufacturer's approval letter, a sample warranty, and gallons per square in writing.

Payment Schedule (recommended option)

Milestone	Amount
No deposit required	$0.00
When materials are loaded on the roof and cleaning & sealing are complete	$90,470.00
Upon completion of the job	$90,470.00
Total	**$180,940.00**

If a different option is chosen, the same percentages apply to that option's total.

Warranty & Care

- Manufacturer warranty matched to the option chosen; 20 to 30-year systems carry a no-dollar-limit (NDL) full-system warranty covering labor and materials.
- No upcharge for the warranty. Delivered in writing within 30 days of completion.

- Free roof inspection and any needed maintenance every year for the first 3 years, with a written report.
- Your roof record (proposal, warranty, product data, photos, mil readings and maintenance reports) is available to your whole management team in one link.

Exclusions & Terms

Not included: Interior repairs or ceiling tiles; Structural deck replacement (priced separately if found); HVAC equipment work beyond curb flashing

- Pricing is valid for 30 days from the proposal date.
- Work is scheduled when the weather allows; coatings are not applied in rain, dew or below the manufacturer's minimum temperature.
- Any hidden conditions found during work (wet insulation, deck damage) will be shown to the owner and priced in writing before that work is done.
- McCurdy Coatings carries general liability and workers' compensation insurance; certificates are available on request.
- Warranty is subject to final payment and the manufacturer's terms.

Acceptance

Check the option you choose, sign and date below. Signing authorizes McCurdy Coatings to schedule the work under the terms above.

☐	Silicone Renewal — 10-Year Warranty	$117,940.00
☐	Silicone Renewal — 15-Year Warranty	$145,240.00
☐	Silicone Renewal — 30-Year NDL Full System	$180,940.00

Property Owner / Authorized Agent

Signature

Printed name

Title

Date

McCurdy Coatings

Signature

Mike McCurdy, Owner

Date

Mike McCurdy Roofing Inc. · CSLB License #477152. Contractors are required by law to be licensed and regulated by the Contractors' State License Board which has jurisdiction to investigate complaints against contractors if a complaint regarding a patent act or omission is filed within four years of the date of the alleged violation. A complaint regarding a latent act or omission pertaining to structural defects must be filed within 10 years of the date of the alleged violation. Any questions concerning a contractor may be referred to the Registrar, Contractors' State License Board, P.O. Box 26000, Sacramento, California 95826.