Commercial Roof Renewal Proposal

Prepared for **Dana Ortiz**, Valley Logistics Partners LLC

Property	4800 E Jensen Ave, Fresno, CA 93725
Roof area	42,000 sq ft · existing modified bitumen (approx. 18 years old)
Proposal #	MCC-2026-0142
Date	October 24, 2026
Valid until	November 23, 2026
Prepared by	Mike McCurdy · (650) 952-0233

OUR RECOMMENDATION
Silicone Restoration — 15-Year
15-year warranty · 30 dry mils · $145,240.00

VS. TEAR-OFF & REPLACE
Save $316,760.00
about 68.6% less, no tear-off, no business shutdown

Summary

Your roof membrane is aged but still watertight over most of the building. A silicone restoration seals it, reflects Central Valley heat and adds up to 20 years of warranted life without a tear-off or closing the warehouse.

What We Found

We walked the full roof on Oct 20. The modified bitumen is chalking and cracking from sun exposure, with seam lifts at wall transitions and ponding in two low areas near the center drains. Core samples showed dry insulation.

Key issues

- Sun damage and surface cracking across most of the field area
- Seam lifting at parapet walls and around HVAC curbs
- Ponding water (1–2 in.) at two center drains
- Four drain strainers missing or broken

Scope of Work

- Safety setup: fall-protection plan, rooftop access control and daily site cleanup.

- Inspect and core-sample the roof; mark and replace wet or damaged insulation found.
- Power-wash the full roof surface and let it dry completely.
- Repair seams, blisters, splits and flashings; reinforce penetrations, drains and transitions with fabric.
- Apply primer where the substrate needs it (adhesion-tested first).
- Apply the silicone coating system in multiple passes to the specified dry-mil thickness.
- Mil-gauge check across the roof, final walk-through with owner and photo documentation.
- Register the manufacturer warranty and hand over the warranty and maintenance packet.

Investment Options

Every option is a full silicone restoration over your existing roof. Thicker systems carry longer manufacturer warranties.

Option	Dry mils	Warranty	Investment	$ / sq ft
Silicone Restoration — 10-Year	20	10 yrs	$117,940.00	$2.81
Silicone Restoration — 15-Year RECOMMENDED	30	15 yrs	$145,240.00	$3.46
Silicone Restoration — 20-Year NDL	40	20 yrs	$180,940.00	$4.31

Included in every option

- Replace 6 roof drain strainers and clear drain lines — $1,110.00
- Re-flash 14 HVAC curbs with reinforced silicone detail — $1,330.00

Renewal vs. Replacement

	Tear-off & replace	McCurdy renewal (Better)
Estimated cost	$462,000.00	$145,240.00
Business disruption	Weeks of noise, debris, open roof	Building stays open
Landfill waste	Old roof hauled to landfill	Existing roof stays in place
Energy	Depends on new membrane	Reflective white surface lowers roof temperature
Future	Start over at end of life	Re-coat to extend life again
You save		$316,760.00 (68.6%)

Replacement estimate uses a typical regional tear-off rate for comparison only.

Payment Schedule (recommended option)

Milestone	Amount
Deposit at signing (30%)	$43,572.00
Balance at substantial completion	$101,668.00
Total	**$145,240.00**

If a different option is chosen, the same percentages apply to that option's total.

Warranty & Care

- Manufacturer material warranty matched to the option chosen.
- McCurdy Coatings workmanship warranty: 2 years.
- Optional yearly roof check-up and drain cleaning plan keeps the warranty in good standing.

Exclusions & Terms

Not included: Interior repairs or ceiling tiles; Structural deck replacement (priced separately if found); HVAC equipment work beyond curb flashing

- Pricing is valid for 30 days from the proposal date.
- Work is scheduled when the weather allows; coatings are not applied in rain, dew or below the manufacturer's minimum temperature.
- Any hidden conditions found during work (wet insulation, deck damage) will be shown to the owner and priced in writing before that work is done.
- McCurdy Coatings carries general liability and workers' compensation insurance; certificates are available on request.
- Warranty is subject to final payment and the manufacturer's terms.

Acceptance

Check the option you choose, sign and date below. Signing authorizes McCurdy Coatings to schedule the work under the terms above.

☐	Silicone Restoration — 10-Year	$117,940.00
☐	Silicone Restoration — 15-Year	$145,240.00
☐	Silicone Restoration — 20-Year NDL	$180,940.00

Property Owner / Authorized Agent

Signature

Printed name

Title

Date

McCurdy Coatings

Signature

Mike McCurdy, Owner

Date

Mike McCurdy Roofing Inc. · CSLB License #477152. Contractors are required by law to be licensed and regulated by the Contractors' State License Board which has jurisdiction to investigate complaints against contractors if a complaint regarding a patent act or omission is filed within four years of the date of the alleged violation. A complaint regarding a latent act or omission pertaining to structural defects must be filed within 10 years of the date of the alleged violation. Any questions concerning a contractor may be referred to the Registrar, Contractors' State License Board, P.O. Box 26000, Sacramento, California 95826.